AL SAEED ENTERPRISES (PVT) LTD

Construction Material Calculator

Covered area daalein — cement, sarya, ret aur bajri ki andazan miqdaar aur kharcha nikal aayega (grey structure).

Peeli (yellow) cells mein apni maloomat daalein — baqi sab khud hisaab ho jayega. Fill the light-yellow cells; everything else calculates automatically.

Total covered area (sq ft)	2,330
Wastage allowance	5%

Material	Unit	Qty per sq ft	Quantity needed	Rate (Rs per unit)	Amount (Rs)
Cement (50 kg bag)	bag	0.42	1,028	1,450	1,490,600
Steel / Sarya Grade 60	kg	3.80	9,297	259	2,407,923
Sand (coarse)	cft	1.80	4,404	-	-
Crush / Bajri	cft	1.35	3,303	-	-
Bricks / Blocks (optional)	nos	0.0	0	-	-
				TOTAL	**3,898,523**

Steel in tons	9.30

Quantities are rough estimates for grey structure only; actual needs depend on the structural drawings. Confirm with your engineer before buying. alsaeedpvt.com · 0336-8240008 · 388-A Lasbela House, Garden West, Karachi